



पुण्यश्लोक अहिल्यादेवी होळकर
सोलापूर विद्यापीठ
॥ विद्याया शंपन्ना ॥
NAAC Accredited-2015
'B' Grade (CGPA 2.62)


पुण्यश्लोक अहिल्यादेवी होळकर सोलापूर विद्यापीठ, सोलापूर

Punyashlok Ahilyadevi Holkar Solapur University, Solapur

केगाव, सोलापूर-४१३२५५ महाराष्ट्र (भारत)

दुरध्वनी क्र.०२१७-२७४४७७१-७३ (११ लाईन्स) फॅक्स-०२१७-२३५१३००

संकेतस्थळ : <http://su.digitaluniversity.ac.in> ई-मेल: fao@sus.ac.in



केंद्रीय खरेदी विभाग

जा.क्र.पुअहोसोविसो/विवले/केंखवि/२०१९/१५१

दिनांक 28 NOV 2019

प्रति

विषय: प्रस्तुत विद्यापीठाच्या क्रीडा व शारीरिक शिक्षण संकुलाकरीता अंडरग्राऊंड वॉटर टँक तयार करणेसाठी दरपत्रके मागविणेबाबत.

महोदय/महोदया,

उपरोक्त विषयास अनुसरून आपणास कळविण्यात येते की, प्रस्तुत विद्यापीठास क्रीडा व शारीरिक शिक्षण संकुलाकरीता अंडरग्राऊंड वॉटर टँक तयार करून घेण्यासाठी सोबत जोडलेले **Schedule B** प्रमाणे दरपत्रके मागविण्यात येत आहेत.

तरी आपले दरपत्रक नमूद केलेल्या तारखेपूर्वी कार्यालयीन वेळेत पोहोच करावीत. दरपत्रकासंदर्भात सविस्तर माहिती खालीलप्रमाणे आहे.

अ.क्र	तपशील	दिनांक	वेळ	ठिकाण
१	दरपत्रके प्रकाशित करण्याचा दिनांक व वेळ	२८/११/२०१९	सायं ४.००	वित्त व लेखा विभाग पुण्यश्लोक अहिल्यादेवी होळकर सोलापूर विद्यापीठ, सोलापूर-४१३२५५
२	दरपत्रके स्विकारण्याची दिनांक व वेळ	२८/११/२०१९	सायं ४.००	
३	दरपत्रके सादर करणे अंतिम दिनांक व वेळ	०६/१२/२०१९	सायं ६.००	
४	दरपत्रके उघडण्याचा दिनांक व वेळ (शक्य झाल्यास)	०७/१२/२०१९	सकाळी १२.००	

वरील कामाचे दरपत्रक, सुचना सोलापूर विद्यापीठाच्या <http://su.digitaluniversity.ac.in> या संकेतस्थळावर Quotation या शिर्षकाखाली उपलब्ध आहे.


(सी.ए. श्रेणिक शहा)

वित्त व लेखा अधिकारी

सुचना व अटी

१. दरपत्रक हे सील बंद पाकीटातून कार्यालयीन वेळेत मा. वित्त व लेखा अधिकारी, पुण्यश्लोक अहिल्यादेवी होळकर सोलापूर विद्यापीठ, सोलापूर सोलापूर-पुणे महामार्ग केगांव, सोलापूर-४१३२५५ यांच्या नावाने पोहोचतील अशा बेताने पाठवावीत.
२. पाकीटावरती दरपत्रके अंडरग्राऊंड वॉटर टँक तयार करणेसाठी दरपत्रके असा स्पष्ट उल्लेख करावा.
३. शॉप अॅक्ट, पॅन कार्ड, GST Registration, ग्राहक सुची यांची छायांकीत प्रत जोडणे आवश्यक आहे.
४. दिलेल्या मुदतीनंतर म्हणजेच उशिरा आलेल्या दरपत्रकांचा विचार केला जाणार नाही. तसेच अटी व शर्ती अपूर्ण असलेली दरपत्रके मंजूर करण्यात येणार नाहीत.
५. दरपत्रके हे देताना आपले दर सर्व करासहित (Including GST / Excluding GST) किंमत असा स्पष्ट उल्लेख करावा. (आवश्यकतेनुसार त्या त्या वेळी विद्यापीठात येवून विद्यापीठात पोहोच करणे/ आणून देणे) पुरवठा हा विद्यापीठ कार्यालयात स्व:खर्चाने करावा लागेल.
६. कोणतेही कारण न देता दरपत्रके स्वीकारणे अथवा नाकारणे याबाबत विद्यापीठाने अधिकार राखून ठेवलेले आहेत. पुरवठा आदेशानुसार साहित्याचा पुरवठा नसेल तर पुरवठादाराचा ठेका रद्द करण्याचा अधिकार विद्यापीठास राहिल.
७. वरील दरपत्रकसंदर्भात काही शंका / अडचणी असल्यास विद्यापीठाच्या ०२१७-२७४४७७०-७४(Ext. २७८) या दूरध्वनी क्रमांकावर संपर्क साधावा.
वरील सुचना व अटी मान्य आहेत.

पुरवठादाराची स्वाक्षरी व शिक्का



SOLAPUR UNIVERSITY , PUNYASHOLK AHILADEVI
HOLKAR SOLAPUR UNIVERSITY , SOLAPUR
Krida Sankul and Health Care Center
SCHEDULE "B"
(BASED ON P.W.D. . S.S.R. 2019-2020)

BILLS OF QUANTITIES
UNDER GROUND WATER TANK

Tender Inviting Authority : Punyashlok Ahilyadevi Holkar Solapur University Solapur.

Name of Work: CONSTRUCTION OF KRIDA SANKUL & HEALTH CARE CENTER UNDER GROUND WATER TANK AT PUNYASHLOK AHILYADEVI HOLKAR SOLAPUR UNIVERSITY SOLAPUR.

Contract No : Civil work

Select

%

Bidder Name :

SCHEDULE OF WORKS UNDER GROUND WATER TANK

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Punyashlok Ahilyadevi Holkar Solapur University Solapur.

CONSTRUCTION OF KRIDA SANKUL & HEALTH CARE CENTER UNDER GROUND WATER TANK AT PUNYASHLOK AHILYADEVI HOLKAR SOLAPUR UNIVERSITY SOLAPUR

SCHEDULE BILLS OF QUANTITIES PART - 1

SUMMARY OF COST OF CIVIL WORKS

SCHEDULE OF ABSTRACT UNDER GROUND WATER TANK

BASED ON SSR FOR THE YEAR 2019-2020 (SOLAPUR DIVISION)

Sr. No	ITEM OF WORK	ESTIMATE COST	FIGUR IN WORDS
1.	EXCAVATION (item no - 1, 2, 3)	RS 11,785.75	Rupees Eleven Thousand Seven Hundred Eighty Five & Paise Seventy Five Only
2.	Reinforcement cement concrete (item no - 4,6,7,8,12)	RS 1,02,048.62	Rupees One Lacs Two Thousand Forty Eight & Paise Sixty Two Only
3.	Brick Masonry (item no - 5)	RS 80,830.13	Rupees Eighty Thousand Eight Hundred Thirty & Paise Thirteen Only
4.	Inside Outside Plastering (item no -9,10,11)	RS 52,175.96	Rupees Fifty Two Thousand One Hundred Seventy Five & Paise Ninety Six Only
5.	Royalty charges (item no - 13)	RS 1,122.00	Rupees One Thousand One Hundred Twenty Two Only
6.	Laboratory testing charges (item 14)	RS 16,600.00	Rupees Sixteen Thousand Six Hundred Only
TOTAL		RS. 2,64,562.46	
Rs = 2,64,563.00 (Two Lacs Sixty Four Thousand Five Hundred Sixty Three Only)			
Quoted Percentage lwe ready to work as per		% above/below/Estimated rate's in Schedule 'B'	
Quoted Percentage			
Quoted Percentage in Words		2,468.00	Rupees Two Thousand Four Hundred Sixty Eight Only
Add Insurance towards Labour @ 1.00%		29,621.00	Rupees Twenty Nine Thousand Six Hundred Twenty One Only
Add G.S.T. on Roads & Bridges @ 12.00% on Rs.2,47,962.46 (Amount Excluding Royalty & Lab Testing)			

Signature of Contractor with seal

No. of Corrections

The Registrar

Tender Inviting Authority : P.A.H. SOLAPUR UNIVERSITY, SOLAPUR.

Name of Work : CONSTRUCTION OF KRIDA SANKUL AND HEALTH CARE CENTER UNDER GROUND WATER TANK OF P.A.H.SOLAPUR UNIVERSITY,SOLAPUR

Contract No : Civil work

SCHEDULE OF WORKS UNDER GROUND WATER TANK

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No	Description of work	No. or Qty	Unit	Figure	Estimate Rate		Amount Rs
					Words		
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 meter beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Specification No : Bd.A.1, Page No : 259 164.69)	7.500	Cum.	164.70	Rupees One Hundred Sixty Four & Paise Seventy Only		1,235.25
2	Excavation for foundation in hard murum including removing the excavated material up to a distance of 50 meter beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Specification No : Bd.A.2, Page No : 259 180.43)	25.00	Cum.	180.45	Rupees One Hundred Eighty & Paise Forty Five Only		4,511.25
3	Excavation for foundation in soft rock and old cement and lime masonry foundations including removing the excavated materials up to a distance of 50 meter beyond the building area and stacking as directed including dewatering, preparing the bed for the foundation and necessary back filling, with available earth, murum, ramming, watering including shoring and strutting etc. complete. (Specification No : Bd.A.4, Page No : 259 345.12)	17.500	Cum.	345.10	Rupees Three Hundred Forty Five & Paise Ten Only		6,039.25
4	Providing and laying Cast in situ/Ready Mix, cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including balling out water, formwork, laying/pumping, compacting and curing etc. complete, with fully automatic micro processor based Programmable Logic Controller without Supervisory Control and Data Acquisition enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer etc. complete With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc) (using natural sand 50 percent and crushed sand 50 percent). (using NATURAL SAND). Rate as per R. A. No. - 1 (Specification No : Bd.E.1, Page No : 287 - 288)	3.750	Cum	5,088.70	Rupees Five Thousand Eighty Eight & Paise Seventy Only		19,082.63
5	Providing second class burnt brick masonry with conventional / Indian Standard type bricks in cement mortar 1:6 in foundations and plinth of inner walls / in plinth of external walls including balling out water manually, striking joints, on unexposed faces, racking out joints on exposed faces and watering complete. Rate as per R. A. No. - 2 (Specification No : Bd.G.1, Page No : 313)	12.180	Cum	6,636.30	Rupees Six Thousand Six Hundred Thirty Six & Paise Thirty Only		80,830.13

Signature of Contractor with seal

No. of Corrections

The Registrar

Tender Inviting Authority: P.A.H. SOLAPUR UNIVERSITY, SOLAPUR.

Name of Work: CONSTRUCTION OF KRIDA SANKUL AND HEALTH CARE CENTER UNDER GROUND WATER TANK OF P.A.H.SOLAPUR UNIVERSITY, SOLAPUR

Contract No : Civil work

SCHEDULE OF WORKS UNDER GROUND WATER TANK

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr.No	Description of work	No or Qty	Unit	Figure	Estimate Rate words	Amount R
6	Providing and laying cast in situ / Ready Mix cement concrete M-20 of trap / granite /quartzite/gneiss metal for reinforced cement concrete beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based Programmable Logic Controller without Supervisory Control and Data Acquisition enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc) (using natural sand 50 percent and crushed sand 50 percent). (using NATURAL SAND). Rate as per R. A. No. - 8 (Specification No : Bd.F.6 B -7, Page No : 300 - 301 3 8-40)	0.910	Cum	10,149.85	Rupees Ten Thousand One Hundred Forty Nine & Paise Eighty Five Only	9,236.36
7	Providing and laying cast in situ / Ready Mix cement concrete M-20 of trap/ granite / quartzite/ gneiss metal for reinforced cement concrete slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, laying / pumping, compaction, finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided and curing, etc. complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based Programmable Logic Controller without Supervisory Control and Data Acquisition enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc) (using natural sand 50 percent and crushed sand 50 percent). (using NATURAL SAND). Rate as per R. A. No. - 3 (Specification No : Bd.F.8 B -7, Page No : 302 - 303 3 8-40)	3.310	Cum.	12,249.15	Rupees Twelve Thousand Two Hundred Forty Nine & Paise Fifteen Only	40544.69
8	Providing and fixing in position thermo mechanically treated FE-500 steel bar reinforcement of various dia for reinforced cement concrete pile caps, Ton footings, foundations, slabs, beams, columns, canopies, staircases, newels, chajjas, lintels, pardis, copings, fins, arches, etc. as per detailed designs, drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete. Rate as per R. A. No. - 4.(Specification No : Bd.F.17, Page No : 306)	0.431	Cum.	65,833.50	Rupees Sixty Five Thousand Eight Hundred Thirty Three & Paise Fifty Only	28,374.24

Signature of Contractor with seal

No. of Corrections

The Registrar

Tender Inviting Authority: P.A.H. SOLAPUR UNIVERSITY, SOLAPUR..

Name of Work: CONSTRUCTION OF KRIDA SANKUL AND HEALTH CARE CENTER ENTRANCE GATE OF P.A.H.SOLAPUR UNIVERSITY, SOLAPUR

Contract No : Civil work

SCHEDULE OF WORKS UNDER GROUND WATER TANK

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No	Description of work	No. or Qty	Unit	Figure	Estimate Rate words	Amount Rs
9	Providing internal cement plaster 20 millimetre thick in single coat in cement mortar 1:4 without neeru finish to concrete, brick surface, in all positions including scaffolding and curing, etc. complete. Rate as per R. A. No. - 5 (Specification No : Bd.L.4, Page No : 368)	50.400	Sq. m	427.50	Rupees Four Hundred Twenty Seven & Paise Fifty Only	21,546.00
10	Providing sand faced plaster externally in cement mortar using approved screened sand in all positions including base coat of 15 millimetre thick in cement mortar 1:4 using waterproofing compound at one kilograms per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment of 6 to 8 millimetre thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days, scaffolding, etc. complete. Rate as per R. A. No. - 9 (Specification No : Bd.L.7, Page No : 369)	37.600	Sq. m	734.00	Rupees Seven Hundred Thirty Four Only	27,598.40
11	Providing fine cement finish 1.5 millimetre thick over green plaster surface including scaffolding, curing, etc. complete. Rate as per R. A. No. - 7 (Specification No : , Page No :)	50.400	No.	60.15	Rupees Sixty & Paise Fifteen Only	3031.56
12	Providing and fixing reinforced cement concrete cover of size 90 centimeter X 45 centimeter with frame over inspection chamber, etc. complete. - (Specification No : , Page No : 4810.71)	1.00	No.	4, 810.70	Rupees Four Thousand Eight Hundred Ten & Paise Seventy Only	4810.70
13	Royalty charges for various building construction bonafied materials which are used for government bonafied works and for which Royalty charges are to be paid by the contractor. (This Item is to be paid to the contractor only after he pays the Royalty amount to Revenue department and produces the required voucher.) SSR 2019-20 I/P 3/0 141.34 (Specification No : , Page No :)	7.940	Cum.	141.34	Rupees One Hundred Forty One & Paise Thirty Four Only	1122.24
14	Laboratory testing charges for various materials required for items of work, on the basis of testing frequency and charges fixed by Vigilance and Quality Control Circle, Pune. SSR 2019-20 I/P 4/0 16600.00 (Specification No : , Page No :)	1.00	Job	16,600.00	Rupees Sixteen Thousand Six Hundred Only	16,600.00

Signature of Contractor with seal

No. of Corrections

The Registrar